

## Artisan Tiny House on Wheels (THoW) Moveable Home Standard Package

### Includes:

#### Drawings:

- Digital (printable) PDF file
- SIP, shop assembly drawings digital (printable) PDF file.

#### Structural Insulated Panels (SIP) enclosure package:

(7/16 OSB | 3-1/2 Expanded polystyrene (EPS) foam insulation | 7/16 OSB)

- Floor - 4-1/2" SIP R-16 Insulation
- Walls - 4-1/2" SIP R-16 Insulation
- Roof - 4-1/2" SIP R-16 Insulation
- All panels cut to plan and routed for wiring and lumber install.
- All door and window openings cut and routed for lumber install,
- Lumber *ONLY* Bevel cut as needed, does not include all of the lumber as you can purchase it locally for less cost.
- Custom designed trailer for use with SIP Package.
- Accessory Package including: SIP Screws, bolts and hardware for floor connection, spray foam, Mastic and mastic gun

### Optional:

- Complete lumber package including all lumber.
- Thicker SIPs for increased R-values or higher snow loads
- Platinum Foam for R-20 insulation in the 4-1/2" panel
- Zink Borate OSB for better insect and mold control.
- On-site training / raising party for owner builders

### Excludes:

- Lumber (#2 and better Kiln Dried), for bottom and top plates and window and door openings.
- Interior framing, wall finishes, paint, stain, etc.
- Plumbing systems and fixtures, electrical systems and fixtures
- Cabinets and counters, floor finishes, interior doors and trim
- Labor to erect on-site